



Hinsdale County Road 30
Chip Seal and Bike Lane Project
Addendum #1
April 16, 2024

The following questions were asked during the bid review process. Responses are in **bold**.

1. Can you confirm shot rate for the 1/2" chips and 3/4 chips? It appears to be low? **After additional consultation, the following shot rates will be used on the project. Line Item 411-10216 (Emulsified Asphalt) (CRS@P) has been revised to 74,000 gallons as indicted on the attached revised bid schedule (dated April 16, 2024), which should be used for bidding the project.**
 - For 1/2 -inch chip sealing, a shot rate range of 0.44 to 0.46 gal./sq. yd shall be applied
 - For 3/4-inch chips, a shot rate range of 0.54 to 0.56 gal./sq.yd. shall be applied
2. What is the warranty period for the project ? **One year from the date of final project acceptance by Hinsdale County.**
3. There is reference to liquidated damages in Section 108 but we don't see any. **No liquidated damages have been assigned to the project.**
4. There are conflicting dates in the project documents. When are bids due to Hinsdale County? **Bids are due to Hinsdale County by 5:00 pm on Monday, April 22, 2024.**

Contractor shall acknowledge receipt of this addendum and include this acknowledgement with their bid to be considered as compliant with the requirements of the Request for Proposal.

Printed Name

Signature

Date

ATTACHMENT: Revised Bid Schedule dated April 16, 2024

CR 30 BIKE LANE AND CHIP SEAL OVERLAY

CDOT PROJECT # MTF C630-001

REVISED BID SCHEDULE - April 16, 2024

CONTRACT ITEM NO.	DESCRIPTION	UNIT	QUANTITY	UNIT COST	TOTAL
201-00000	Clearing, Grubbing	L.S.	1		
202-04002	Clean Culvert	EACH	18		
203-00012	Unclassified Excavation (Complete in Place)	CY	310		
208-00000	Erosion Control (including management)	DAY	30		
208-00041	Rock Check Dam	EACH	238		
208-00106	Sediment Removal	Hour	8		
212-00700	Organic Fertilizer	Pounds	660		
212-00702	Biotic Soil Amendments (Hydraulic Applied)	Pounds	7,700		
212-00703	Humate	Pounds	440		
304-06007	Aggregate Base Course (Class 6)	CY	270		
212-00707	Seeding (Native) (hydraulic)	ACRE	2.2		
306-01000	Reconditioning	SY	1,000		
409-04015	Cover Coat Material (TYPE II) (1/2")	SY	80,000		
409-04015	Cover Coat Material (TYPE IV) (3/4")	SY	80,000		
411-10216	Emulsified Asphalt (Rapid Setting) (Polymerized)(CRS2P)	GAL	74,000		
411-10253	Emulsified Asphalt (CSS-1H) (Fog Coat)(Diluted)	GAL	9,000		
614-00012	Sign Panel (Class II)	SF	60		
614-00220	Steel Sign Post(2.5 x 2.5 Tubing))	LF	120		
620-00020	Sanitary Facility	EACH	1		
625-00000	Construction Surveying	L.S.	1		
626-00307	Mobilization/Demobilization	L.S.	1		
626-01114	Public Information Management	DAY	45		
627-00005	Pavement Marking Paint	GAL	360		
630-00012	Traffic Control Management	DAY	30		
630-00012	Traffic Control inspections (Weekends)	DAY	8		
700-00001	Force Account	Each	1	\$ 5,000.00	\$ 5,000.00

TOTAL CONSTRUCTION COST

--